MYSORE DIVISION.

Dated 27th March 1909.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 16th April 1909, for constructing a combined dispensary and in-patient wards with out-houses at Nanjangud. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1910.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a combined dispensary and in-patient wards with out-houses at Nanjangud," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	*Items of work.*	*Per*	*Quantity.*
	Dispensary and wards.		
1.	Earthwork, excavation and filling basement	C. yd.	126
2.	Concrete work to foundation	C. ft.	1,182
3.	Burnt stone in chunam foundation and basement	„	3,078
4.	Burnt brick in chunam, superstructure	„	5,598
5.	Armoured concrete work	„	257
6.	Teakwood moulds for preparing armoured concrete, etc.	L. S.	
7.	Iron work for chowkets, etc., to be locally made	„	
8.	Burnt stone slabs	S. ft.	999
9.	Reinforced concrete work with portland cement for roofing	C. ft.	689
10.	Iron work including fright and fitting charges	Cwt.	19·34
11.	Threading and finishing tierods of main roof, complete	L. S.	
12.	Finishing tierods, etc., with bolts and nuts, complete, of curved roof and angle iron.	Each	88
13.	Finishing the inside projections of doors and windows with portland cement wash up to 6 feet high.	L. S.	
14.	Chunam plastering	Sqr.	86·51
15.	Filling in the angles in rooms	L. S.	
16.	Flooring with Cuddappah slabs on 3-inch concrete bed and cement pointing, etc.	Sqr.	15·22
17.	Raising masonry walls over concrete slab, complete	L. S.	
18.	Teakwood pannelled doors	S. ft.	226
19.	Teakwood windows, pannelled shutters outside and glazed shutters inside with iron bars, complete.	„	184
20.	Teakwood ventilators with glazed shutters	„	62
21.	Whitewashing, two coats	Sqr.	49·83
22.	Colorwashing, two coats	„	36·68
23.	Ornamental iron finials	Each	12
24.	Painting to iron work	L. S.	
25.	Chocolate painting	Sqr.	9·43
26.	Inscription	L. S.	
27.	Levelling ground	„	
28.	Constructing compound wall of the type approved by the Chief Engineer.	„	
29.	Latrine	„	
30.	Rain water pipes	„	
31.	Excavating well	„	
32.	Constructing cisterns in examination and compounding room	„	

No.	Items of work.	Per	Quantity.
	Kitchen.		
1.	Earthwork, excavation and filling basement	C. yd.	8
2.	Burnt stone in chunam foundation and basement	C. ft.	290
3.	Burnt brick in chunam superstructure	„	293
4.	Burnt stone slabs	S. ft.	31
5.	Iron work including fright and fitting charges	Cwt.	4·21
6.	Chunam plastering	Sqr.	5·74
7.	Teakwood pannelled doors	S. ft.	18
8.	Whitewashing, two coats	Sqr.	2·54
9.	Colorwashing, two coats	„	2·76
10.	Chocolate painting	„	1·45
11.	Roofing with 1st class Mangalore tiles excluding reepers ...	„	2·06
12.	Ridge tiles set in mortar	R. ft.	15
13.	Ventilating tiles	Each	4
14.	Flooring with concrete with smooth plastering	C ft.	35
15.	Teakwood windows, ordinary, with battened shutters	S. ft.	4
16.	Bolting rafters, ridges, drilling holes, bolts and nuts	Each	1
17.	Holding, down bolts, 18 inches long and ¾″ diameter with anchor plates.	„	4
18.	Folding angle iron reepers, drilling holes, revet and revetting, complete.	„	48
19.	Constructing chimney in kitchen	L. S.	...
	Dead-house.		
1.	Earthwork, excavation and filling basement	C. yds.	17
2.	Burnt stone in chunam foundation and basement	C. ft.	537
3.	Burnt brick in chunam superstructure	„	309
4.	Burnt stone slabs	S. ft.	83
5.	Iron work including fright and fitting charges	Cwt.	7·6
6.	Chunam plastering	Sqr.	5·61
7.	Flooring with Cuddappah slabs, on 3″ concrete bed and cement pointing.	„	1·50
8.	Whitewashing, two coats	„	5·61
9.	Chocolate painting	„	1·02
10.	Roofing with 1st class Mangalore tiles excluding reepers ...	„	3·57
11.	Ridge tiles set in mortar	R. ft.	17
12.	Ventilating tiles	Each	2
13.	Burnt stone slab table sloping towards centre nicely dressed and polished for dissecting	C. ft.	10
14.	Teakwood battened doors	S. ft.	18
15.	Teakwood windows battened with iron bars, glazed shutters inside, etc., complete.	„	9
16.	Teakwood large window frames fitted with gauge wire netting ...	„	24
17.	Folding down bolts, 18 inches long and ¾ inches diameter with anchor plates.	Each	4
18.	Folding angle iron reepers, drilling holes, revet and revetting, complete.	„	88
19.	Honey-comb work	Sqr.	2·50
20.	Wrought iron pipe for connecting the table	R. ft.	12

B. SUBBA RAO,
Executive Engineer.

SANITARY DIVISION.

Dated 31st March 1909.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Sanitary Division, up to 12th April 1909, 2 P.M., for laying out extensions for Shimoga Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1909.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office at Bangalore, between the hours of 11 A.M. and 4 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for laying out the extensions for Shimoga Town;" in default of which tenders will be rejected.